

CASE STUDY

Maroochydore Road Upgrade Stage 3

In June 2006 FRH Contracting was awarded a contract for the third stage of the Maroochydore Road Upgrade works.

Incorporated in the project design were several concrete crib retaining walls. Concrib had been involved with the construction of similar structures incorporated in the first and second stages of this important Sunshine Coast roads improvement program. So, it was pleasing that FRH appointed Concrib to construct the walls for the third stage. The crib walls on this project were substantial structures with heights up to 4.5 metres with a 20 kPa surcharge loading above the wall in some areas. A total of about 350 square metres of walling was built.

As well as completing the work on time and within budget, Concrib were able to refine the structural design of the walls, thereby enabling a cost saving to be passed to the client. The completed walls were finished with landscape planting and mulch over the top to create a pleasing presentation.

Need a crib retaining wall?

Talk to the experts at Concrib. We have the knowledge and experience to tackle a variety of earth stabilisation, and construction projects.

Please contact us on (07) 3375 1800, or visit our website at www.concrib.com.au to see more examples of our work.

